

## Planning and Building Department 250 Frank H. Ogawa Plaza, 2<sup>nd</sup> Floor, Oakland, CA 94612 INFO: (510) 238-3443 | https://www.oaklandca.gov/permitquestions

# PLANNING APPLICATION FOR SB 9 MINISTERIAL TWO-UNIT RESIDENTIAL DEVELOPMENT AND/OR PARCEL SUBDIVISION RESULTING IN TWO LOTS<sup>1</sup>

	GENERAL INFORMATION		
AP	PLICANT'S NAME/COMPANY:		
PR	OPERTY ADDRESS:		
	STING USE OF PROPERTY:		
DE	SCRIPTION OF PROPOSAL:		
_			
	LECT TYPE(S) OF PROPOSED SB-9 DEVELOPMENT religibility details and additional regulations for SB 9, please refer to the Zoning Criteria Checklist starting on page 8.		
	<b>LOT SPLIT:</b> SPLITTING ONE SINGLE-FAMILY LOT OF AT LEAST 2,400 SQUARE FEET INTO TWO LOTS OF APPROXIMATELY EQUAL SIZE.		
	HOUSING UNITS: A HOUSING DEVELOPMENT CONTAINING UP TO TWO RESIDENTIAL UNITS ON THE EXISTING SINGLE-FAMILY LOT WITHOUT SPLITTING THE LOT OR UP TO TWO UNITS ON EACH NEWLY CREATED LOT IF THE LOT SPLIT OPTION ABOVE HAS ALSO BEEN SELECTED.		

## **APPLICATION PROCESS**

This application is a first step for the review of SB 9 related proposals. Completion of this application and checklist is required. Proposals are also subject to Planning (OMC Title 17), Subdivision (OMC Title 16), and Building (OMC Title 15) Code requirements. All applicable Planning, Subdivision, and Building Code requirements not addressed by this application, and consistent with State Law, must be met before this application is approved. Once Planning has reviewed the application and has determined it meets Planning and Subdivision requirements, the applicant may apply for the Building permit and approval of the final Parcel Map. HOW TO APPLY:

- COMPLETE ALL REQUIRED INFORMATION, CHECKLIST, DOCUMENTS, AFFIDAVITS, AND PLANS AS OUTLINED ON PAGE 2.
- SUBMIT A ZONING WORKSHEET AND UPLOAD YOUR COMPLETED SB 9 APPLICATION THROUGH THE CITY OF OAKLAND'S
   ONLINE PERMIT CENTER: https://aca-prod.accela.com/oakland/default.aspx

<sup>&</sup>lt;sup>1</sup> Senate Bill 9 (SB 9) added Sections 65852.21 and 66411.7 to the Government Code and amended Government Code Section 66452.6 to permit two residential units on lots zoned single family and requires local agencies to ministerially approve a parcel map for an urban lot split on single family lots in the City that meet the requirements in this application. SB 450 subsequently amended these government code provisions.

## SUBMITTAL REQUIREMENTS CHECKLIST

In addition to completing this form, please submit all applications and plans electronically to the Online Permit Center

using the Zoning Worksheet linked here: https://aca-prod.accela.com/oakland/customization/common/launchpad.aspx ☐ Color Photographs of Property and Adjacent Properties ☐ Plans (See pages 4-6 for more detailed Plan, Survey, and Related requirements) ☐ Full Boundary and Topographic Survey ☐ Site Plan (existing and proposed) ■ Landscape Plan Demolition Plan (Required only if the project proposes any building demolition) ☐ Floor Plans (existing and proposed) Elevations ☐ Cross-Sections (Required only if the proposal is located on a lot with a slope of 20% or more) ☐ Tree Survey (Required only if the proposal involves a Tree Preservation/Removal Permit, see pp. 5 and 12) ☐ Grading Plan (Required only if the proposal includes site grading) ☐ Preliminary Post-Construction Stormwater Management Plan Creek Protection Permit (Required only if the proposal is located on a Creekside property, see p. 13) ☐ CALGreen Checklist (See page 13) ☐ Objective Design Standards for One-Family and Two- to Four-Family Residential and Mixed-Used Developments https://www.oaklandca.gov/files/assets/city/planning-amp-building/documents/sp/design-standards/objectivedesign-standards-for-one-family-and-two-to-four-family-residential-and-mixed-use-developments.pdf ☐ Supplemental Submittal Requirements for Tentative Parcel Map for urban lot Splits or Condo Duplexes² (https://www.oaklandca.gov/Planning-Building/Permit-Process-Overview/Planning-Building-Forms/Supplemental-Planning-Forms) ☐ Post-Project Owner Occupancy Affidavit for the parcel subdivision resulting in two lots (Signed and Notarized) stating that the owner intends to occupy one of the units as their principal residence for three (3) years from the date of final parcel map approval (or alternatively stating that the owner is a community land trusts or qualified nonprofit corporations, as defined in Revenue and Taxation Code §§ 402.1(a)(11)(C)(ii), 214.15 respectively) Affidavit Regarding Tenancy and Ellis Act Status (Signed and Notarized) Stating that: The proposed development would not require demolition or alteration of affordable housing including deedrestricted affordable housing, rent-controlled housing, housing that was withdrawn from the rental market in the last fifteen (15) years, or any affordable housing occupied by a tenant in the past three (3) years prior to this application The proposed development is not for a property where Ellis Act was used to evict tenants in the last fifteen (15) years A tenant has not resided in the property in the last three (3) years prior to this application ☐ Preliminary Title Report or deed not more than 60 days old

CITY OF OAKLAND – SB-9 APPLICATION PAGE 2 8/15/2025 REV.

<sup>&</sup>lt;sup>2</sup> Tentative Parcel Map Submittal Requirements: <a href="https://www.oaklandca.gov/files/assets/city/planning-amp-building/documents/pc/supp-forms/tentative-parcel-map-supplemental-submittal-requirements-1-4-lots-fillable.pdf">https://www.oaklandca.gov/files/assets/city/planning-amp-building/documents/pc/supp-forms/tentative-parcel-map-supplemental-submittal-requirements-1-4-lots-fillable.pdf</a>

## PROPERTY OWNER & APPLICANT INFORMATION

Owner:			
Owner Mailing Address:			
City/State:		Zip:	
Phone No.:	Alt. Phone No.:	E-mail:	
To be completed only if Applicant is not	the Property Owner:		
I authorize the applicant indicated below	to submit the application on my behalf		
		Signature of Property Owner	
Applicant (Authorized Agent), if differen	t from Owner:		
City/State:		Zip:	
		E-mail:	
Variance, or exception from any other Ci		any administrative review, Conditional Use Permit, subject of this application. I understand further that enant to the property.	
I certify that I am the Applicant and that the information submitted with this application is true and accurate to the best of my knowledge and belief. I understand that the City is not responsible for inaccuracies in information presented, and that inaccuracies may result in the revocation of planning permits as determined by the Planning Director. I further certify that I am the Owner or purchaser (or option holder) of the property involved in this application, or the lessee or agent fully authorized by the owner to make this submission, as indicated by the owner's signature above. I understand the consent of all owners must be provided.			
I am aware that every section of this application form and each submittal component listed within are necessary for an accurate and complete review of my proposal. I understand that any failure to submit the information and/or materials, or to respond to requests for clarifying information, in a timely manner may render the application inactive and that periods of inactivity on the applicant's part do not count towards statutory time limits applicable to the processing of this application.			
I understand that the proposed project and/or property may be subject to other laws, codes, regulations, guidelines, restrictions, agreements, or other requirements of other public agencies within or outside of the City of Oakland, and that the project and/or property may also be subject to requirements enforced by private parties. I am aware that the City recommends that I become fully aware of any other potential requirements before I submit this application and that I comply with all other requirements prior to commencing the proposed project.			
I HEREBY CERTIFY, UNDER PENALTY OF PERJURY, THAT I HAVE READ THE ABOVE AND THAT ALL THE INFORMATION PROVIDED IN THIS APPLICATION IS TRUE AND CORRECT.			
Signature of Owner or Authorized Agent Date			

## **ZONING PLAN REQUIREMENTS**

## PLAN SETS FOR PLANNING PERMIT Include north arrow, date prepared and scale. Acceptable drawing scales are: 1/4'' = 1', 3/16'' = 1', 1/8'' = 1', and 1'' = 10'. Include the name, email and phone number of a person preparing the plan. Show all encroachments into the public Right-of-Way. Include space for zoning stamp. ☐ (a) FULL BOUNDARY AND TOPOGRAPHICAL SURVEY Must be no more than 3 years old from the time of submittal – date of survey must be included. Must be prepared by a California State Licensed Land Surveyor or by a Civil Engineer with a license number below 33966 (licensed prior to January 1, 1982). **Include the wet stamp and signature** of the Land Surveyor or Civil Engineer who prepared the survey. Include the applicable surveyor's statement in accordance with the Professional Land Surveyors Act. In addition to paper copies, the survey must also be submitted in digital format. Required for building/addition with new or replacement footprint within 3 feet of a property line: ☐ Applicable line survey with field-verifiable monuments set or found by the surveyor. ☐ Location, dimensions, & dimensions to property line of existing and proposed buildings & similar structures within 3 feet of the relevant property line(s). Required for building/addition with new or replacement footprint on a lot with a slope of 20% or more: ☐ Site topography for all areas of proposed work. ☐ (b) SITE PLAN • Two site plans: one existing, labeled "Existing Site Plan" and one proposed, labeled "Proposed Site Plan" ☐ Location and dimensions of all property boundaries. Location and dimensions of all existing and proposed buildings, decks, stairs, and patios. Dimensions of all existing and proposed building setbacks from property lines. Location, dimensions, and paving materials of all existing and proposed adjacent sidewalks, curbs, curbcuts (including curb-cuts on adjacent neighbor's lots), and streets. Location and dimension of all existing and proposed driveways, garages, carports, vehicle parking spaces, bicycle parking spaces, maneuvering aisles, wheel-stops, pavement striping/marking, and directional signage. Indicate existing and proposed paving materials. Location, height, and building materials of all existing and proposed fencing and walls. Location, height (including top and bottom elevation measurements), and building materials of all existing and proposed retaining walls. Location and size based on diameter at breast height (dbh) of all existing trees and indication of any

(continued)

contours overlaid with proposed roof plan and indicating roof ridge spot elevations.

☐ Location and size of storage area for recycling containers and screened utilities.

☐ Show any building to be demolished, both historic and non-historic.

☐ Location of drainage ways, creeks, and wetlands.

trees to be removed, include trees on neighboring properties that are within 10 feet of construction.

Roof plan showing roof slope and direction, and location of mechanical equipment, ducts, and vents.
 For projects located on a lot with a slope of 20% or more: Show existing and proposed topographic

## **ZONING PLAN REQUIREMENTS (continued)**

	Zorano i Exa in Exponentia (continued)
(c)	<ul> <li>LANDSCAPE PLAN</li> <li>☐ Indicate any existing landscaping and new landscaping.</li> <li>☐ Indicate the size, species, location, and method of irrigation for all plantings.</li> <li>☐ Include the square footage of new landscaping. If over 500 square feet of new landscaping please provide all requirements per the Water Efficiency Landscape Ordinance (WELO), visit <a href="https://water.ca.gov/Programs/Water-Use-And-Efficiency/Urban-Water-Use-Efficiency/Model-Water-Efficient-Landscape-Ordinance">https://water.ca.gov/Programs/Water-Use-And-Efficiency/Urban-Water-Use-Efficiency/Model-Water-Efficient-Landscape-Ordinance</a></li> <li>☐ Include all existing and proposed groundcovers, driveways, walkways, patios, and other surface treatments.</li> </ul>
	FLOOR PLAN Include complete floor plan of all floors of entire building, including existing and proposed work. Label all rooms (e.g., bedroom, kitchen, bathroom), and include dimensions of room sizes. Show locations of all existing and proposed doors, walls, and windows, including any window schedule (recess, sash and trim material, manufacture). Show location of and distance to all adjacent property boundaries. Label and identify location of existing Residential Facility and proposed Residential Facility.
	Show all structure elevations (front, sides and rear) that will be affected by the proposed project. For additions/alterations: label existing and new construction, as well as items to be removed. Identify all existing and proposed exterior materials - including roofing, roof eaves, eave brackets, siding doors, trim, sills, windows, retaining walls, fences, and railings. Show details of proposed new exterior elements.  Show any exterior mechanical, duct work, and/or screened utility boxes.  Include dimensions for building height (from grade to pitch) and wall length.
	CROSS SECTIONS (required only for buildings or additions located on a lot with a slope of 20% or more) Include all critical cross sections, including at least one passing through the tallest portion of the building.  Include floor plate and roof plate elevation heights.  Location of and distance to all adjacent property boundaries.  Label the location of the cross-sections on the site plan.
_	TREE SURVEY (required only for projects which involve a Tree Preservation/Removal Permit) Include north arrow, date prepared and scale (Tree Survey should be drawn to the same scale as the Site Plan). Include the name & phone number of person preparing the plan(s). As appropriate or required, include the stamp & "wet signature" of any licensed architect, landscape architect, surveyor and/or civil
	engineer preparing final plans.  Indicate the size (dbh), species, and location of all protected trees within 30 feet of development activity on the subject lot, regardless of whether the protected trees are included on any tree preservation/removal permit application.  Label all protected trees that are located within 10 feet of construction (including trees located on
	neighbor's properties or the adjacent public right-of-way) with the matching number or letter from the Tree Preservation/Removal Permit application (see page 12 of this application).

## (continued)

# **ZONING PLAN REQUIREMENTS (continued)**

(h) <b>G</b> R	ADING PLAN (required only if the project proposes any site grading)
☐ Sh	ow proposed grading plan and/or map showing existing and proposed topographic contours (this may
be	combined with the Site Plan for small projects with only minor grading).
☐ Inc	lude an erosion & sedimentation control plan.
☐ Inc	lude a summary table of all proposed excavation, fill, and off-haul volumes.
(i) Prel	iminary Post-Construction Stormwater Management Plan* (required only for "Regulated Projects"
subject	t to NPDES C.3 stormwater requirements [see page 11 for more information])
	Show location and size of new and replaced impervious surface.
	Show directional surface flow of stormwater runoff.
	Show location of proposed on-site storm drain lines.
	Show preliminary type and location of proposed site design measures, source control measures, and stormwater treatment measures.
	Show preliminary type and location of proposed hydromodification management measures (if
_	applicable).
* P	Please refer to the Stormwater Supplemental Form for more information concerning NPDES C.3
rec	quirements. The Stormwater Supplemental Form must also be submitted with the application.

1. PROJECT CALCULATIONS: EXISTING RESIDENTIAL FACILITY					
	Existing Pre-Project	Demolition	New Proposed	Total Post-Project	% Change (Existing/Total)
Number of Dwelling Units					
Existing Residential Facility (if modifying):					
Floor area (sq. ft.)					
Footprint (sq. ft.)					
Building height (ft.)					
Onsite Parking Spaces (number) N/A			N/A		

2. PROJECT CALCULATIONS: PROPOSED RESIDENTIAL FACILITIES					
Existing Lot Area (sq. ft.)	Existing Lot Area (sq. ft.)				
Existing Lot Frontage (ft.)					
Lot Area of Each New Lot:	(sq. ft. and %)				
Lot #1: Total Lot Area					
Lot #2: Total Lot Area					
Lot Frontage for Each New Lot:	(ft.)				
Lot #1: Total Frontage					
Lot #2: Total Frontage					
New Dwelling Units – Total Floor Area:	(sq. ft.)				
DU #1					
DU #2					
DU #3					
DU #4					
Total for all DUs					
New Dwelling Units – Height (list for each):	(ft.)				
DU #1					
DU #2					
DU #3					
DU #4					
Location of New Dwelling Unit(s):	# of units				
Attached to Existing					
Interior Conversion					
New Duplex					
New Detached					
Number of New Onsite Parking Spaces					

8/15/2025 REV.

## **ZONING CRITERIA CHECKLIST**

Applicant's Name:	Project Address:
	velopment and/or parcel subdivision resulting in two lots may only be granted if the applicant can check ate) to EACH of the following:
1) ALL SB-9 PROPOSALS	
YES NO	The existing lot is located within the RH single-family residential zone.
YES NO N/A	If the existing lot is split between City of Oakland and a neighboring jurisdiction, applicant has executed a memorandum of agreement or any other required permit from both jurisdictions allowing one jurisdiction to conduct project review. (Select N/A if lot is entirely within the City of Oakland)
YES NO NO	The proposed development will result in no more than two (2) residential units per lot, including any ADUs or JADUs, but no less than one (1) residential unit per lot.
YES NO NO	The proposed development would not require demolition or alteration of affordable housing including deed-restricted affordable housing, rent-controlled housing, and housing that was withdrawn from the rental market in the last 15 years.
YES NO NO	The proposed development would not demolish or alter any of the existing structure if a tenant has resided in the property in the last three (3) years prior to this application.
YES NO NO	The development is not proposed for a property where the Ellis Act was used to evict tenants in the last fifteen (15) years.
YES NO NO	The proposed development is located outside of Historic Districts including S-7 and S-20 Designated Historic Districts and Areas of Primary Importance (API), and not designated as National, State or Local Historic Resource or Landmark.
YES NO NO	Proposed development is located outside of environmentally sensitive areas and satisfies the requirements specified in Government Code Section 65913.4(a)(6)(B)-(K), as that section read on September 16, 2021:  - A coastal zone
	- Prime farmland or farmland of statewide importance - Wetlands
	<ul> <li>Within a very high fire hazard severity zone, as determined by CalFire, unless fire hazard mitigation measures are incorporated</li> </ul>
	- Delineated earthquake fault zone
	- 100-year Flood Zone
	<ul> <li>Within a regulatory floodway</li> <li>Lands identified for conservation in an adopted natural community conservation plan</li> </ul>
	- Habitat for protected or endangered species such as Alameda Whipsnake - Lands under conservation easement
YES NO NO	Any resulting residential units will not be used as a short-term rental facility (less than 30 consecutive days); rentals must be for more than 30 consecutive days.

(continued)

## **ZONING CRITERIA CHECKLIST (continued)**

Objective Site Design Requirements:				
YES NO N/	The project meets all applicable objective design standards included in the City of Oakland Objective Design Standards Checklist for One-Family and Two- to Four-Family Residential and Mixed-Use Developments.			
YES NO NO N/	The project design is consistent with the City of Oakland Fire Code, including but not limited to California Fire Code Section 503, Fire Apparatus Access Roads.			
YES NO NO N/	All portions of new structures have a setback of at least four (4) feet from the rear and side lot lines. <sup>3</sup> (Select N/A if setbacks are not required according to the footnote.)			
YES NO N/	If adding to an existing building or increasing the existing building's footprint, the existing building has a setback of at least four (4) feet from the rear and side lot lines. (Select N/A only if not adding to or modifying an existing building footprint.)			
YES NO NO N/	Proposed development meets regularly required front lot setbacks ( <i>Select N/A only if these standards preclude creation of up to two units of eight hundred (800) square feet.</i> )			
YES NO N/	Proposed development includes one additional off-street parking space for each of the newly created units (Select N/A only if the proposal is located within a ½-mile walking distance from a high-quality transit hub and additional parking is not required.)			
YES NO N/	For all other development standards (including maximum dwelling unit size and height), the proposed development conforms with the regularly required standards of the zone where the project is proposed. However, in no event the regularly required standards of the zone shall preclude a residential dwelling unit(s) of 800 square feet at the minimum. (Select N/A only if these standards preclude creation of such dwelling unit.)			
	If "N/A" selected, describe the standard(s) that preclude creation of up to two units of eight hundred (800) square feet:			
2) <u>REQUIRED FOR</u>	R ALL SB-9 PROPOSALS THAT INCLUDE PARCEL SUBDIVISION RESULTING IN TWO LOTS			
YES NO	The proposal splits one single-family residential lot into no more than two residential lots of approximately equal size (50/50 percent division) or no greater than 60/40 percent division.			
YES NO	The proposed development will result in no more than two (2) residential units per lot, but no less than one (1) residential unit per lot, including any ADUs and JADUs.			
YES NO	Each resulting lot area after the lot split is a minimum of 1,200 square feet in size.			
YES NO	YES NO The lot was not created through a previous SB 9 parcel subdivision, or the same owner did not subdivide an adjacent lot via SB 9.			
(continued)				

<sup>3</sup> Setbacks are not required if (1) a structure is rebuilt in the same location and to the same exact dimensions as the original structure or (2) imposing the setback would preclude the construction of up to two units or preclude either of the two units from being at least 800 square feet in floor area.

## **ZONING CRITERIA CHECKLIST (continued)** YES NO The lot was not previously a part of a parcel map subdivision of three (3) or four (4) created by the same owner, owner's relative, or any corporate entity associated with the owner, so that the SB 9 application would result in quartering. YES NO The proposed development meets frontage and legal access requirements for subdivisions pursuant to O.M.C. Title 16. YES NO The proposal submission includes the Supplemental Submittal Requirements for Tentative Parcel Map. YES NO The owner intends to reside a resulting or existing residential units for at least three (3) years from the date of Final Parcel Map approval. (Exception for community land trusts and qualified nonprofit corporations, as defined in Revenue and Taxation Code Sections 402.1(a)(11)(C)(ii) and 214.15 respectively.) Required Additional Acknowledgements: YES N/A Proposed development must meet the Tentative Parcel Map Checklist Requirements. 4 (Select N/A only if not *subdividing the lot.)* YES 🗌 Completion of this zoning criteria is a first step in the application approval process and does not fulfill all requirements of the Oakland Municipal Code related to public health, safety, and welfare for adding new residential unit(s). Once Planning has approved this application, the applicant still needs to meet Building, Fire, and any other Municipal Code requirements.

Staff may require additional substantial evidence to be provided on the record or as affidavits by the applicant in support of certain checklist items. Please see the above checklist for the required affidavits. Other evidence may be

Owner understands that legally binding affidavits must be signed, notarized, and submitted with this application.

Owner understands that once an SB 9 parcel subdivision resulting in two lots has been approved and completed, the resulting lot(s) will not be eligible for any more than two (2) residential units per lot, including any ADUs or

New and existing dwelling units must be built to allow for separate conveyance (i.e. built to standards allowing for independent ownership of the separate units if desired in the future), pursuant to State law, including but not limited to having separate meters, HVAC systems, separate entrances, and include any additional Building

Date

I have reviewed the above checklist and certify that the project conforms to all applicable criteria above.

Applicant's Signature

Date

requested. If evidence is not provided the application may not be approved.

YES 🗌

YES 🗌

YES 🗌

YES 🗌

Reviewer's Signature

JADUs.

Code requirements.

<sup>&</sup>lt;sup>4</sup> Tentative Parcel Map Submittal Requirements: <a href="https://www.oaklandca.gov/files/assets/city/planning-amp-building/documents/">https://www.oaklandca.gov/files/assets/city/planning-amp-building/documents/</a>
pc/supp-forms/tentative-parcel-map-supplemental-submittal-requirements-1-4-lots-fillable.pdf

## **IMPERVIOUS SURFACE INFORMATION**

The San Francisco Bay Regional Water Quality Control Board reissued the Municipal Regional Stormwater Permit (MRP 3.0). The MRP went into effect July 1, 2022 with further changes to the Regulated Project Thresholds effective July 1, 2023. **PROJECT CHARACTERISTICS:** (check one) (1) The one single-family home project will create or replace 10,000 ft<sup>2</sup> or more of new/existing impervious surface area\* (2) The project will create or replace 5,000 ft<sup>2</sup> or more of new/existing impervious surface area including pavement maintenance or paving upgrade projects\*. If you checked (1) or (2), the project is a "Regulated Project" and must comply with NPDES C.3 stormwater requirements. You must submit a completed Stormwater Supplemental Form MRP 3.0 and a Preliminary Post-Construction Stormwater Management Plan with your application (see page 6). (3) The project will create or replace 2,500 ft<sup>2</sup> or more but less than 10,000 ft<sup>2</sup> of new/existing impervious surface for one single-family home OR 2,500 ft<sup>2</sup> or more but less than 5,000 ft<sup>2</sup> of new/existing impervious surface. If you checked (3), site design measures to retain stormwater on site are required. Refer to the City's "Overview of Provision C.3" for more information. https://www.oaklandca.gov/Planning-Building/Permit-Process-Overview/Municipal-Regional-**Stormwater-Permit-Resources** ☐ (4) None of the above \*Impervious Surface = Any surface that cannot be effectively (easily) penetrated by water. Permeable paving (such as permeable concrete and interlocking pavers) underlain with permeable soil or permeable storage material, and green roofs with a minimum of three inches of planting media, are not considered impervious surfaces. Do not include existing impervious surface to be replaced as part of routine maintenance/repair activities when calculating the amount of new/replaced impervious surface. **HAZARDOUS WASTE AND SUBSTANCES STATEMENT** GOVERNMENT CODE SECTION 65962.5(f): Before the city accepts as complete an application, the applicant shall consult the list of hazardous waste and substance facilities and sites and shall submit a signed statement to the city indicating whether the project is located on a site that is included on any of the lists compiled pursuant to this section and shall specify any list. Please refer to the following State-maintained websites: https://calepa.ca.gov/SiteCleanup/CorteseList/ and http://geotracker.waterboards.ca.gov/ or contact the CalEPA at (916) 323-2514 to determine if your project is on any list of properties containing hazardous waste, toxic substances or underground fuel tanks. NOTE: YOU MUST REVIEW ALL LISTS ☐ I have reviewed ALL the lists and my site does not appear on them (sign below). City Verification Required My site does appear on the list(s) (please complete the following statement and sign below). HAZARDOUS WASTE AND SUBSTANCES STATEMENT Name of applicant: Applicant address: Phone number: Address of site on list: Local agency (city/county): Specify any list pursuant to Section 65962.5 of the Gov. Code: Regulatory identification number: Date of list: Status of regulatory action:

Date

Signature of Owner or Authorized Agent

#### TREE PRESERVATION ORDINANCE

Pursuant to the Tree Preservation Ordinance (§12.36 O.M.C.) a Tree Preservation/Removal Permit is required for any proposed construction activity (including buildings, driveways, paths, decks, construction vehicle routes, sidewalk improvements, & perimeter grading) within 10 feet of a Protected Tree, even if such trees are not being removed or if they are located on a neighbor's property.


#### The following are "Protected Trees" under the Tree Preservation Ordinance:

- a. Any Coast Live Oak tree that is larger than 4 inches dbh\*
- Any tree (except Eucalyptus) that is larger than 9 inches dbh\* (Eucalyptus trees and up to 5
  Monterey Pines per acre are not considered Protected Trees under this section. Monterey Pines
  must be inspected and verified by the Public Works Agency Tree Division prior to their removal.
  Contact the Tree Division at (510) 615-5934 for more information or to schedule an inspection)
- c. Any tree of any size located in the public right-of-way (including street trees)



#### **I, THE APPLICANT/OWNER, ATTEST THAT:** (check one)

- There are <u>no</u> existing Protected Trees anywhere on the subject property or within 10 feet of the proposed construction activities\*\* (including neighbor's properties or the adjacent public right-of-way).
- There <u>are</u> Protected Trees on the subject property or within 10 feet of the proposed construction activities, and their location is indicated on the site plan and landscape plan **and** *(check one)*;
  - (a) No Protected Trees are to be removed *and*No construction activity will occur within 10 feet of any Protected Tree.
  - (b) No Protected Trees are to be removed *and*Construction activity will occur within 10 feet of any Protected Tree.
  - ☐ (c) Protected Trees will be removed.



**DESCRIPTION OF TREES:** (Identification numbers and letters must be consistent with the Tree Survey – See submittal requirements.)

Trees proposed for removal				Trees <u>not</u> proposed for removal but located within 10 feet of Construction Activity	1
#	Species	dbh*	#	Species	dbh*
1			Α		
2			В		
3			С		
4			D		
5			E		

Reason(s) for removal/impacting of trees: \_\_\_

<sup>\*</sup> **dbh**: "diameter at breast height" is determined by measuring the trunk at 4'-6" from the ground. Multi-trunked trees are measured by combining the diameters of all trunks at 4'-6" from the ground.

<sup>\*\*</sup> Construction Activity: Any proposed building, driveway, path, deck, construction vehicle route, sidewalk improvement, grading, or demolition.

#### **CREEK PROTECTION ORDINANCE**

Pursuant to the Creek Protection, Storm Water Management and Discharge Control Ordinance (§13.16 O.M.C.) a Creek Protection Permit is required for any proposed construction activity occurring on a Creekside property. The extent to which your development will be regulated by the Creek Protection Ordinance depends upon the location and type of proposed work.

#### WHAT IS A CREEK?

"A **Creek** is a watercourse that is a naturally occurring swale or depression, or engineered channel that carries fresh or estuarine water either seasonally or year around."

A creek must include the following two components:

- 1. The channel is part of a contiguous waterway. It is hydrologically connected to a waterway above or below the site or is connected to lakes, the estuary, or Bay. Creek headwaters, found at the top of watersheds, are connected in the downhill direction. Additionally, creeks in Oakland are often connected through underground culverts. Only the open sections of creeks are subject to the permit, and
- 2. There is a creek bed, bank and topography such as a u-shape, v-shape channel, ditch or waterway (identified through field investigation, topographical maps, and aerial photos). To help with identification in the field a creek may also have the following features (the absence of these features does NOT mean there is no creek):
  - A riparian corridor, which is a line of denser vegetation flowing downhill. This is sometimes missing due to landscaping or vegetation removal practices, landslide, or fire.
  - The channel has a bed with material that differs from the surrounding material (i.e. more rocky, or gravelly, little or no vegetation).
  - There are man-made structures common to waterways (e.g., bank retaining walls, trash racks, culverts, inlets, rip rap, etc.)

#### I, ATTEST THAT: (check one)

(1)	I do not know whether there is a Creek on or near the proposed project site. I have submitted a request for a Cree Determination by the City of Oakland (separate form and fee required).		
(2)	No Creek exists on or near the project site; (check one)		
	☐ (a	) Based on my review of the characteristics of the project site, as well as all relevant maps and plans, and the Creek Determination criteria provided in the "What is a Creek?" section above; or	
	☐ (b	) Based on the attached report prepared by a relevant licensed professional.	
	Howev	ver, if the City determines that a Creek exists on or near the project site, a Creek Protection Permit is required.	
(3)	A Cree	ek DOES exist on or near the project site and; (check one)	
	□ (a	The proposed project only entails <u>interior</u> construction and/or alterations (including remodeling), and therefore requires a <u>Category 1 Creek Permit</u> (this is a no fee permit and only requires distribution of educational materials); or	
	☐ (b	The proposed project entails exterior work that <u>does not</u> include earthwork and is located more than 100 feet from the centerline of the Creek, and therefore requires a <u>Category 2 Creek Permit</u> (this permit requires a site plan and distribution of educational materials); or	
	□ (c)	The proposed project entails (a) exterior work that is located between 20 feet from the top of the Creek bank and 100 feet from the centerline of the Creek, and/or (b) exterior work that includes earthwork involving more than three (3) cubic yards of material located beyond 20 feet from the top of the Creek bank, and therefore requires a <u>Category 3 Creek Permit</u> (this permit requires a site plan and creek protection plan and may require environmental review); or	
	<b>□</b> (d	) The project entails exterior work conducted from the centerline of the Creek to within 20 feet from the top of the Creek bank, and therefore requires a <u>Category 4 Creek Permit</u> (this permit requires a site plan and creek	

The Creek Permit requirements for your project are subject to verification by the City of Oakland and may differ from what you have indicated above. Additionally, you are responsible for contacting and obtaining all required permits from the relevant state and federal permitting agencies for Category 3 and Category 4 Creek Permits.

protection plan and may require environmental review and a hydrology report).

## **GREEN BUILDING ORDINANCE**

If GreenPoint Rater is required, this sheet must be filled in and signed by the GreenPoint Rater along with the checklist and is due at the Intake appointment or over the counter approval. The submittal will not be accepted if this is not complete at intake and the applicant will need to come back for another appointment.

If there is an addition and/or remodel that total over 1,000 ft², the project is over 1,000 ft², or there is a new unit; a GreenPoint Rater is required. Pursuant to the Ordinance 'Sustainable Green Building Requirements for Private Development,' (Chapter 18.02 of the Oakland Municipal Code), a Green Building Permit is required for any proposed construction activity within certain categories. The extent to which your development will be regulated by the Green Building Ordinance depends upon the location, type of proposed work, and size of proposed work.

Α.	PROPERTY ADDRESS:	
В.	PROJECT TYPE OF DEVELOPMENT (check one):	<ul> <li>□ New Construction and Lot Split</li> <li>□ New Construction without Lot Split</li> </ul>
C.	TOTAL NEW AND ALTERED FLOOR AREA (square fee	et):
	<ul><li>(2) I have reviewed the Green Building Ordinance and the required additional green building materials with this</li><li>(3) I have reviewed the Green Building Ordinance and the</li></ul>	e project <u>DOES NOT</u> fall within the list of applicable project types. e project <u>MUST</u> comply with the ordinance, AND I am submitting the <u>application</u> . e project <u>MUST</u> comply with the ordinance, AND I am submitting the <u>application</u> , but a GreenPoint Rater or LEED AP is not required as the
D.	Name of Greenpoint Rater (required for Greenpoint I	Rated Projects)*:
	Name of LEED Accredited Professional (AP) (require	ed for LEED projects)*:
	MAILING ADDRESS:	
	PHONE: E-MAIL:	
	RATING SYSTEM: # OF POINTS THE	PROJECT IS ANTICIPATED TO RECEIVE:
E.	GREEN BUILDING FEATURES NOT SHOWN ON PLAN	NS BUT PART OF CHECKLIST (include additional sheets if needed):
se		rested financial interest in the project other than my green building ilding checklist, and attest that to the best of my knowledge the proposed Building Ordinance and attain green building certification.
X	gnature of the GreenPoint Rater or LEED Accredite	
Si	gnature of the GreenPoint Rater or LEED Accredite	ed Professional Date
The ari	is permit is granted upon the express condition that the permittee shall be sing out of permittee's failure to perform the obligations with respect to t demnify, save and hold harmless the City, its officers and employees, fror y bodily injuries, disease or illness or damage to persons and/or property	the No. 13040 C.M.S., "Sustainable Green Building Requirements for Private Development." responsible for all claims and liabilities arising out of work performed under this permit or his permit. The permittee shall, and by acceptance of this permit agrees to defend, in and against any and all suits, claims or actions brought by any reason for or on account of sustained or arising in the construction of the work performed under this permit or in the othis permit. Violations of the provisions of the Green Building Ordinance are subject to
TC	D BE COMPLETED BY CITY STAFF:	
		Case Planner's Name:
No	ote to Case Planner: Please route a copy of this form to the gree	en building coordinator in the Planning and Zoning Division.

CITY OF OAKLAND – SB-9 APPLICATION PAGE 14 8/15/2025 REV.

# **EQUITABLE CLIMATE ACTION PLAN CONSISTENCY CHECKLIST FOR SB 9**

YES NO	The project is an infill development that creates more units of housing within an existing single-family neighborhood.
YES NO	If the project is located within a "Transit Accessible Area" as defined in the Planning Code, the project shall result in no more than one parking space per newly created dwelling unit.
YES NO	The project complies with the City of Oakland Green Building Ordinance, as applicable and as demonstrated above.
YES NO	The project reduces demolition waste from construction and renovation and facilitates material reuse in compliance with the Construction Demolition Ordinance (Chapter 15.34 of the Oakland Municipal Code).
YES NO NO	If the project is located within the City-designated Very High Fire Hazard Severity Zone, the project incorporates wildfire safety requirements such as creation of defensible space around the home, pruning, clearing, and removal of vegetation, and replacement of fire resistant plants?